

Appendix B: Proposed Construction at Cross-Culverts

APPENDIX B

Proposed Construction at Cross Culverts

Culvert ID	TDA	Culvert Size	Mile post	Direction Affected	Construction Activity
1	A1	Unknown	15.95	Southbound	Replace 190 ft. culvert, add catch basins
2	A1	18"	16.07	Southbound	Extend west approx. 13 ft., add catch basin
3	A1	18"	16.18	Southbound	Extend west approx. 15 ft., add catch basin
4	A1	18"	16.32	Southbound	Extend west approx. 13 ft., add catch basin
5	A1	24"	16.47	Southbound	Extend west approx. 15 ft., add catch basin
6	A1	18"	16.51	Southbound	Extend west approx. 16 ft., add catch basin
7	A1	Unknown	16.55	Southbound	Extend west approx. 16 ft., add catch basin
8	A2	Unknown	16.70	Southbound	Construct detention vault on west side
16	C1	12"	18.57	Both	Extend west approx. 20 ft., east 15 ft., construct headwall on east side
17	C1	24"	18.79	Southbound	Extend west approx. 22 ft., add catch basin
18	C1	18"	18.96	Southbound	Extend west approx. 25 ft., add catch basin, headwall on east side
19	C1	24"	19.07	Southbound	Extend west approx. 20 ft.
20	C1	30"	19.14	Both	Construct new Forbes Creek fish passage culvert 490 ft. long
21	C1	24"	19.42	Both	Extend east approx. 30 ft., add catch basins
22	C1	24"	19.59	Southbound	Replace 300 ft. culvert, add catch basins
23	C1	24"	19.83	Neither	Replace collection system in NE 116th Street
27	D3	24"	21.23	Southbound	Extend approx. 20 ft. into median, add catch basin
28	D3	30"	21.27	Southbound	Extend approx. 30 ft. into median, replace outfall on west side
29	D3	30"	21.41	Southbound	Extend approx. 35 ft. into median, replace catch basin
30	D4	18"	21.54	Neither	Adjust catch basin in median
34	E2	18"	22.28	Southbound	Extend west approx. 72 ft., add catch basins
35	F1	24"	22.60	Neither	Replace damaged culvert (approx. 152 ft.)
37	F3	24"	22.84	Northbound	Construct collection system and catch basins in shoulder
38	F3	18"	22.90	Northbound	Construct collection system and catch basins in shoulder
39	F3	18"	22.98	Northbound	Construct collection system and catch basins in shoulder
40	F3	18"	23.13	Northbound	Construct collection system and catch basins in shoulder
41	F4	18"	23.18	Both	Construct collection system and catch basins in shoulder
43	F4	24"	23.35	Neither	Construct collection system and catch basins in shoulder with flow splitter

